

KSCSTE - CENTRE FOR WATER RESOURCES DEVELOPMENT AND MANAGEMENT
KUNNAMANGALAM, KOZHIKODE – 673571

TENDER SCHEDULE

Name of work: Changing of damaged roofing sheet of entrance plaza of W H Museum.

P A C: Rs.3,09,937/-

Time of completion: 3Month

Sl. No.	Quantity	Description of items	Estimate Rate (Rs.)	Quoted rate (Rs.)	Amount (Rs.)
1.	4Nos.	Dismantling cement asbestos or other hard board / fibre ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead. Labour charges only.	855.78/E		
2.	302.00m	Supplying of 1"x1" square pipe (16SWG) including cost, conveyance of materials, etc. complete.	125.00/m		
3.	170.00m ²	Labour charges for making frame (Including welding, scaffolding, one coat epoxy painting, two coats painting, etc.)	150.00/m ²		
4.	170.00m ²	Providing & fixing Poly carbonate multi wall plain sheet 8 mm thick as approved by the Engineer in charge and should be supplied in a single length of 12 M or as decide by the Engineer in charge. The sheets shall be fixed using self drilling / self tapping screw of size (5.5x55mm) with EPDM seal complete up to any pitch in horizontal / vertical / curved surface, but excluding the cost of purlins, rafters, trusses, and including cutting to size and shapes where ever required.	1,152.85/m ²		
		Total		
		Add GST 18%			
		Grand total			

I hereby agree to undertake and execute the work @ Rs./-

(In words.....)

Name:

Address:

Signature: